SCHEDULE - B

Name of the Work: Formation of 6th mainroad KEGS Layout from 8th Cross to End in W-18

Tender Notification: EE/H/TEND/03/12-13 date: 02/07/2012
Item No: 07

Sl. No	Description of item	Quantity	Unit	Rate (Rs)	
				In figures	In words
1	Dismantling Mangalore tiles roof and stacking the material within a radius of 50mtrs.-do- A.C. sheet roofing etc., complete as per specifications and direction of the Engineer-in-Charge	40.00	Sqm	46.00	Rupees Forty Six Only
2	Dismantling burnt brick masonry in clay mortar / lime mortar / cement mortar and stacking the bricks within a radius of 50m and removing the debris to a distance upto 200m. Conveying the excavated earth' with a lead of 10KMS etc., complete as per specifications and direction of the Engineer-in-Charge	30.24	Cum	115.00	Rupees One Hundred Fifteen Only
3	Dismantling size stone masonry in clay mortar and stacking the size stone within a radius of 50m and removing the debris to a distance upto 200m etc., complete as per specifications and direction of the Engineer-in-Charge	12.76	Cum	127.00	Rupees One Hundred Twenty Seven Only
4	Earthwork in excavation of foundation of structures as per drawing and technical specification including setting out, construction of shorting and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, back filling the excavation earth to the extent required and utilizing the remaining earth locally for road work complete as per specifications. (i) Ordinary soil – A. Manual Means (i) Depth upto 3m. MORTH etc., complete as per specifications and direction of the Engineer-in-Charge	24.57	Cum	193.00	Rupees One Hundred Ninety Three Only
5	Providing granite slabs of 750mm roughly dressed and fixed in CM 1:6 including fixing curing etc., complete as per specifications and direction of the Engineer-in-Charge	75.60	Sqm	331.00	Rupees Three Hundred Thirty One Only
6	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clodsincluding loading & unloading, cost of labour Conveying the excavated earth to distance of upto 10kms including loading and unloading charges etc., complete as per specifications and direction of the Engineer-in-Charge	117.88	Cum	160.00	Rupees One Hundred Sixty Only

Contractor

Executive Engineer(H)
Bruhat Bangalore Mahanagara Palike

Executive Engineer
Bruhat Bangalore Mahanagara Palike

Sl. No	Description of item	Quantity	Unit	Rate (Rs)	
				In figures	In words
7	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180 kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.86 cum and fine aggregates @ 0.58 cum machine mixed machine mixed concrete laid in layers not exceeding 15 cms.thick well compacted, i+B1n foundation and plinth including cost of all materials, labour, HOM of machinery, curing etc., complete as per specifications and direction of the Engineer-in-Charge	22.50	Cum	4078.00	Rupees Four Thousand Seventy Eight Only
8	Providing and constructing granite/ trap/basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high , bond stones at two m. apart in each course including cost of materials, labour, curing etc., complete as per specifications and direction of the Engineer-in-Charge	81.00	Cum	3384.00	Rupees Three Thousand Three Hundred Eighty Four Only
9	KSRB 4-1.6:Providing and laying in position plain cement concrete of mix M15 with cement @ 240 Kgs, with 20mm and down size graded granite metal coarse aggregtes @ 0.878 cum and line aggregates @ 0.459 cum,machine mixed, concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc., complete as per specifications and direction of the Engineer-in-Charge	18.75	Cum	4630.00	Rupees Four Thousand Six Hundred Thirty Only
10	Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing etc., complete as per specifications and direction of the Engineer-in-Charge	180.00	Sqm	75.00	Rupees Seventy Five Only

Contractor

Executive Engineer,
Bruhat Bangalore Mahanagara Palike
Yelahanka Division

Bruhat Bangalore Mahanagara Palike

Sl. No	Description of item	Quantity	Unit	Rate (Rs)	
				In figures	In words
11	Providing & Laying in position reinforced cement concrete of mix 1:1.5:3 with 20mm (M-20) and down size graded granite metal, machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintles, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutment, pillars, posts, struts, buttresses, string or lacing course, parapets, copying, bed blocks, anchor blocks, plain windown cills, fillets etc complete as per specifications labour HOM of machinery, curing, including cost of providing and fabricating HYSD steel 12mm tor at 15cms c/c (main) and 10mm tor at 20cms c/c (Distribution) & Providing and removing centring and shuttering et., complete as per specifications for 23cms thick drain covering slab etc., complete as per specifications and direction of the Engineer-in-Charge.	180.00	Sqm	1521.00	Rupees One Thousand Five Hundred Twenty One Only
12	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting etc., complete. 450 x 150 x 500mm etc., complete as per specifications and direction of the Engineer-in-Charge.	433.33	Nos	293.00	Rupees Two Hundred Ninety Three Only
13	Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour etc., complete as per specifications and direction of the Engineer-in-Charge.	112.50	Sqm	49.00	Rupees Forty Nine Only

Contractor

Executive Engineer (H)
Bruhat Bangalore Mahanagara Palike

Executive Engineer,
Hebbal Division,
Bruhat Bangalore Mahanagara Palike